



## Project: Truck Washdown Area

### The Problem

This truck washdown area had seen better days..

RPT was called in to rebuild the concrete surface and trench areas.



### The Solution

RPT applied a degreaser to remove any surface oils and contaminants. Spalled areas were saw cut and all loose aggregate was removed until a solid substrate was reached.

**Thortex Floor-Tech SP Primer** and **Thortex Floor-Tech RS** were used to rebuild the concrete. The base and sides of the existing trench drain system were rebuilt at this time as well.

A coat of **Thortex Floor-Tech SP Primer** was applied to the repaired surfaces followed by two (2) coats of **Thortex Chemi-Tech CR** with a slip-deterrent aggregate incorporated into the first coat of **Thortex Chemi-Tech CR**.

RPT / RPT New York

12 Iron Bridge Drive • Collegeville, PA 19426  
800.578.2772 • [www.repairandprotection.com](http://www.repairandprotection.com)